



This particular project was a GSA Government Office Building that was previously FDA lab. Containments (hydro-carbons) were found in the top 1/4" of structural concrete, which prohibited the bond of self-leveling underlayment's that were required for the project progression.

RPG was called to remove the top 1/4" of concrete on the 200,000SF project. As others quickly learned for the size of this project, small rental scarifiers will not be able to accomplish the task.

RPG has several of these specialty machines in our fleet and will make quick work of your scarifying needs. Large scarifiers with the ability to remove a 1/4" of concrete in a single pass are specialty machines that are not available for rent; they require a skilled technician to operate them safely and effectively.

## Concrete Scarifying

Scarifying of Concrete is used for many common problems such as:

- High Spot Elimination
- Concrete Removal For Thicker Flooring Systems
- Containment Removal
- Thin Set Removal